



SUPPORT

(Society for upliftment of People with People's organisation and Rural Technology)

Ref. No. 7663-F/April/2025

Date : 11/04/2025

To
All Vendors/Firm/Agency
India

Sub - Request for Quotation submission towards New Well Construction/Establishment @Pathalgadda, Chatra

Dear All,
Please submit your rate and amount as per prescribed format mentioned below - :

Details of Model Estimate of Low Land Well Dia 12 ft Depth 30ft

SI No	SOR Item No	Particular	Unit	Nos	Area	Depth	Volume cft	Quantity	Rate	Amount
1		Earth cutting work								
		Earth work with hydraulic machine for digging well vide classification of soil item A including remaining the spad to rofe distance up to 50M from the dege of the well all complete for specification and direction of E/S upto 3m depth below G.L								
	12.1.64	In ordinry Soil (0 ft to 20ft)	cum		254.34	20	5086.8	144.10		
	12.1.64	In hard soil for (20ft to 23ft)	cum		254.34	3	763.02	21.62		
	12.1.67	Extra for 4 lift	cum	4				21.62		
	12.1.64	In ordinry soil for (23ft to 26ft)	cum		254.34	3	763.02	21.62		
	12.1.67	Extra for 5 lift	cum	5				21.62		
	12.1.64	In ordinry soil for (26ft to 29ft)	cum		254.34	3	763.02	21.62		
	12.1.67	Extra for 6 lift	cum	6				21.62		
	12.1.64	In ordinry soil for (29ft to 30ft)	cum		254.34	1	254.34	7.21		
	12.1.67	Extra for 7 lift	cum	7				7.21		
2	Non schedule	Dewatering Work	LS							
3	5.3.13	R.C.C curb in foundation	cum	1	66.43	0.67	44.51	1.26		
	5.3.13	R.C.C bend in foundation	cum	2	66.43	0.5	33.22	0.94		
4	5.2.18	Brick Masonry work 75 B work in mud mortar in steining wall		1	66.43	25.33	1682.67	47.67		
	5.7.2	Brick Masonry work 75 A work in C.M (1:6)	cum	1	66.43	5.5	365.37	10.35		
5	12.1.76	Back filling work	cum		89.29	30	2678.8125	75.89		
6	5.3.1.1	P.C.C work								
		Providing P.C.C 150with normal mix of 1:2:4								
		Top of Parapet	cum		66.43	0.25	16.6075	0.47		
7	12.1.74	Plaster work								
		Plaster work 12mm thick C.P(1:6) and all comp. job								
		Inner dia of Parapet wall	sqm		188.4			17.53		
		Outer dia of the Parapet wall	sqm		91.06			8.47		
		Top of Parapet	cum	16	66.43			10.736		

Registered Office

Administrative Office

Branch Offices

Website

DVC Colony, Behind Hanuman Mandir, Hazaribag - 825301(Jharkhand). Phone : 06546-266742, Mob. 9431185632
Email : bsguptahzb@rediffmail.com / supporthzb@gmail.com

BOKARO 216, Co- Operative Colony, B.S. City, Bokaro, Pin - 827001, Mob.: 7004325481
DUMKA At: Masalia, Old PHC Road, PO Ranga Masalia, Dist. Dumka, Mobile-7061153221
KODERMA H/o Amarchand Yadav, Near Middle School, Mahugai, At&PO-Chandwara, Dist. Koderma-825409
WEST SINGHBHUM 2nd Floor, Sanjivani Hospital Complex, Jagannathpur Block, West Singhbhum-833203
Mb.: 7992361799

GIRIDIH Behind Statistical Office, Near Jhanda Chowk, Giridih

www.supportjharkhand.org

Secretary
SUPPORT

8	5.5.4	MS Tor							
		Providing M.S reinforcement 8mm dia to 12mm dia							
		70kg/cu.m	kg		2.20	70		154.13	
									Total
10		Carriage cost of material ...% of total cost					LS		
									Total

Location : Village Barwadih & Dumbi :
Block - Pathalgadda, Chatra, Jharkhand

Project : HRDP

Email Address to submit the quotation

addressed to "SUPPORT" is :

tenderssppt@gmail.com or hardcopy

sealed envelope to SUPPORT ,

Coordination office at DVC Colony,

Hazaribagh by 21st April 2025.

Firm/Agency with GST

registration/proprietorship are only

eligible to apply

9,11/04/2021
(B S Gupta)
(Secretary)
SUPPORT

Secretary
SUPPORT